BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18379/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Pothole filling in ward no 09 in Vidyaranyapura sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K ANIL KUMAR		
				In Figures		In Words
1	335.29	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1605.0	538140.45	Rupees One Thousand Six Hundred Five Only
2	2452.75	Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 finishing the surface to form a smooth continuous surface, all as per clause 3004.2 etc complete as per specifications and directions of engineer in charge of the work	Sqm	319.0	782427.25	Rupees Three Hundred Nineteen Only
					1320567.70	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/2/16